LEGEND

EXISTING KERBLINE

LANDS MADE AVAILABLE FOR THE WORKS

PROPOSED CARRIAGEWAY INLAY

PROPOSED FOOTWAY / TRAFFIC ISLAND

PROPOSED SPEED TABLE

PROPOSED CYCLE TRACK RED SURFACING

LAWNSWOOD PARK

ST BRIGID'S CHURCH ROAD

EXISTING FOOTWAY TO BE REPLACED AT A HIGHER LEVEL TO ADDRESS DRAINAGE PROBLEM WITH EXISTING

TREES TO BE REMOVED (6)

EXISTING OFF-ROAD CYCLE TRACK RETAINED AS-IS

NEW FOOTWAY

NEW FOOTWAY

EXISTING FOOTWAY RETAINED AS-IS

SPEED TABLE: 75 mm HIGH 1:15 SLOPES ON 1.1 m LONG RAMPS

4m

6m

EXISTING OFF-ROAD CYCLE TRACK RETAINED AS-IS

100mm KERB UPSTAND

2m

2m

EXISTING BUS STOP AND SHELTER RETAINED AS-IS

DISHED CROSSING RAMP SLOPE 1 IN 12

5 no. FLEXIBLE BOLLARDS FOR CYCLE TRACK PROTECTION

R 1 m

R 4 m

3m

DISHED CROSSING RAMP SLOPE 1 IN 12

EXISTING CYCLE TRACK RETAINED AS-IS

EXISTING BUS STOP AND SHELTER RETAINED AS-IS

N31 BREWERY ROAD

N11 STILLORGAN DUAL CARRIAGEWAY

LANA

BUS

BUS

BUS

NO ENTRY

NO ENTR

STOP

STOP

dlr Comhairle Contae County Council

Údarás Náisiúnta Iompair National Transport Authority

BARRY TRANSPORTATION

Classon House
Dundrum Business Park,
Dundrum Road,
Dublin 14,
Ireland

Phone: +353 1 485 1400
Email: info@jbbarry.ie

Notes

All levels are referred to Ordnance Survey Datum, Malin Head.
This document should not be relied on or used in circumstances other than those for which it was originally prepared. Barry Transportation accepts no responsibility for this document to any other party other than the party by whom it was commissioned.

Rev.	Date	Drawn	Description	Chk'd	Appr.
P03	20/07/22	SH		TD	PM
P02	07/07/22	SH		TD	PM
P01	14/06/22	SH		TD	PM

Project Title: N11 BREWERY ROAD SAFETY IMPROVEMENT SCHEME

Status: S4

Drawing Title: GENERAL ARRANGEMENT PLAN

Designed: SH	File Name:	Drawing No.	Rev:
Drawn: SH		18406-BT-00-XX-DR-C-00220	P03
Approved: PM	Scale at A1: 1:200		
Checked: TD	Date: 20/07/2022		